



**NOTICE OF A SPECIAL MEETING OF THE PARKS AND RECREATION COMMISSION
OF THE TOWN OF CLARKDALE
THURSDAY, MAY 23, 2024 AT 5:00 PM**

In Person: Clark Memorial Clubhouse, 19 N. Ninth St., Clarkdale AZ

OR

Join Zoom Meeting

<https://us02web.zoom.us/j/85998911182>

Meeting ID: 859 9891 1182

Unless otherwise stated, the public will have physical access to the meeting place 15 minutes prior to the start of the meeting.

Town of Clarkdale Vision

The Town of Clarkdale connects our unique history, proximity to the Verde River, and small-town charm to a future with a vibrant economy.

We cultivate an environment where residents and businesses can thrive; providing services and jobs for our residents and capitalizing upon tourism.

We sustainably enhance our infrastructure, support the arts and education, and develop recreational opportunities to create a bright future for our entire community.

PURSUANT TO A.R.S. §38-431.02, NOTICE IS HEREBY GIVEN that the Parks and Recreation Commission of the Town of Clarkdale will hold a Special Meeting on Thursday, May 23, 2024, at 5:00 PM. Members of the Parks and Recreation Commission will attend either in person, by telephone or via Zoom. A quorum of Town Council members may be present at this meeting; however, they will not deliberate or take any action on items. All members of the public are welcome to attend.

ALL ITEMS ON THIS AGENDA ARE SCHEDULED FOR DISCUSSION AND POSSIBLE ACTION, UNLESS OTHERWISE NOTED.

1. CALL TO ORDER

2. ROLL CALL

3. PUBLIC COMMENT

The Parks and Recreation Commission invites the public to provide comments at this time. Members of the Parks and Recreation Commission may not discuss items that are not specifically identified on the agenda. Therefore, pursuant to A.R.S. §38-431.01, action taken as a result of public comment will be limited to directing staff to study the matter, responding to any criticism, or scheduling the matter for further consideration and decision at a later date. Persons interested in

making comments on a specific agenda item are asked to complete a brief form and submit it to the Clerk or liaison during the meeting. Each speaker is asked to limit their comments to five minutes.

4. UPDATES

A. Track K Park

Update only regarding Track K Park.

B. Caballero Park Wi-Fi

Update only regarding Caballero Park Wi-Fi.

C. Town Park Restrooms

Update only regarding Town Park Restrooms.

D. Tuzigoot RAP - Parking Resurfacing Project

Update only regarding Tuzigoot RAP parking resurfacing project.

E. Lower TAPCO RAP- Viewing Scope

Update only regarding Lower TAPCO RAP viewing scope.

F. Concerts in the Park

Update only regarding Concerts in the Park.

5. MINUTES

A. Approval of Minutes

Discuss, consider and act upon the draft minutes from the Special Meeting held on May 8, 2024.

6. NEW BUSINESS

A. Clarkdale's Old Fashioned Fourth of July Event

Discuss, consider and act upon the Clarkdale Old Fashioned 4th of July event plan with all listed components and awards.

7. FUTURE AGENDA ITEMS

Parks and Recreation Commission may propose items to be placed on a future agenda. This item is for discussion only.

8. ADJOURNMENT

Values

Values are the guiding principles that provide an organization with purpose and direction. The Town of Clarkdale's organizational values are:

COPPER

Customer focused

Open, transparent and equitable

Preserving our history, charm, and environment

Planning for a sustainable future

Economic and social resiliency
Resourceful and innovative

Mission

The Town of Clarkdale serves the community by providing amenities, infrastructure, services, and public safety to enhance quality of life. We are stewards of our history while we sustainably and resiliently plan for the future with an emphasis on community engagement and transparency.

Persons with a disability may request reasonable accommodations by contacting the Town Hall at (928) 639-2400 (TTY: 1-800-367-8939) at least 72 hours in advance of the meeting.



Staff Report

Item Number: 4.A.

<u>Agenda Item:</u>	Track K Park Update only regarding Track K Park.
<u>Staff Contact:</u>	Joni Westcott, Parks and Recreation Director
<u>Meeting Date:</u>	May 23, 2024
<u>Strategic Goal:</u>	Not applicable.
<u>Background:</u>	The Town issued a Second Amendment to the development agreement with the Crossroads at Mingus developer in 2023 allowing them more time to complete the project but adding in an additional year of maintenance as a concession (3 year). The developer was given an extension until June 1 to complete construction. If it is not complete, the Town has the right to take development secured funds and complete the park.
<u>Budget Impact:</u>	No impact.
<u>Recommendation:</u>	No recommendation. Update only.



Staff Report

Item Number: 4.B.

<u>Agenda Item:</u>	Caballero Park Wi-Fi Update only regarding Caballero Park Wi-Fi.
<u>Staff Contact:</u>	Joni Westcott, Parks and Recreation Director
<u>Meeting Date:</u>	May 23, 2024
<u>Strategic Goal:</u>	Not applicable.
<u>Background:</u>	Staff is continuing to pursue the T-Mobile Community Grant to fund the Wi-Fi solar table.
<u>Budget Impact:</u>	No budget impact.
<u>Recommendation:</u>	No recommendation. Update only.



Staff Report

Item Number: 4.C.

Agenda Item: **Town Park Restrooms**
Update only regarding Town Park Restrooms.

Staff Contact: Joni Westcott, Parks and Recreation Director

Meeting Date: May 23, 2024

Strategic Goal: Not applicable.

Background: Bathroom locking systems are not working correctly. Staff have been communicating with Sedona Lock and Key to fix the problem. New stainless-steel sinks/counters will be installed next week, completing the renovation project.

Budget Impact: \$8,924 Park Safety CIP

Recommendation: No recommendation. Update only.



Staff Report

Item Number: 4.D.

Agenda Item: **Tuzigoot RAP - Parking Resurfacing Project**
Update only regarding Tuzigoot RAP parking resurfacing project.

Staff Contact: Joni Westcott, Parks and Recreation Director

Meeting Date: May 23, 2024

Strategic Goal: Not applicable.

Background: Public Works has completed the parking lot resurfacing project. Project total cost was \$17,649, half of which AZ State Parks will reimburse the Town and the remaining will be taken from the Yavapai Apache Nation (Prop 202) donation funds received annually by the Town.

Budget Impact: \$8,824 Yavapai Apache Nation Prop 202 Donation Funds.

Recommendation: No recommendation. Update only.



Staff Report

Item Number: 4.E.

Agenda Item: **Lower TAPCO RAP- Viewing Scope**
Update only regarding Lower TAPCO RAP viewing scope.

Staff Contact: Joni Westcott, Parks and Recreation Director

Meeting Date: May 23, 2024

Strategic Goal: Not applicable.

Background: A viewing scope has been purchased for placement at the Lower TAPCO RAP entrance to allow visitors to learn about the historical culture of the river and surrounding areas. Staff is working with Doug Von Gausig to develop relevant signage for the project that will highlight specific cultural/historical sites, geology, and other river elements on site.

Budget Impact: Estimated total project cost \$10,000 from Yavapai Apache Nation Prop 202 donation funds.

Recommendation: No recommendation. Update only.



Staff Report

Item Number: 4.F.

<u>Agenda Item:</u>	Concerts in the Park Update only regarding Concerts in the Park.
<u>Staff Contact:</u>	Joni Westcott, Parks and Recreation Director
<u>Meeting Date:</u>	May 23, 2024
<u>Strategic Goal:</u>	Not applicable.
<u>Background:</u>	Staff learned this week that of the \$3,500 requested, APS has awarded Parks and Recreation \$1,500 to be used for concerts. The concert budget will be updated to reflect this impact. The first concert begins June 1 at 7 p.m. and features Local Honey, a local reggae band.
<u>Budget Impact:</u>	\$1,500 Concert in the Park donation funds.
<u>Recommendation:</u>	No recommendation. Update only.



Staff Report

Item Number: 5.A.

<u>Agenda Item:</u>	Approval of Minutes Discuss, consider and act upon the draft minutes from the Special Meeting held on May 8, 2024.
<u>Staff Contact:</u>	Joni Westcott, Parks and Recreation Director
<u>Meeting Date:</u>	May 23, 2024
<u>Strategic Goal:</u>	Not applicable.
<u>Background:</u>	Review, discuss, and act upon the May 8, Special Meeting Minutes.
<u>Budget Impact:</u>	None.
<u>Recommendation:</u>	Staff recommends approval of the draft minutes from the Special Meeting held on May 8, 2024.



**MINUTES OF A SPECIAL MEETING OF THE PARKS AND RECREATION COMMISSION
OF THE TOWN OF CLARKDALE
MONDAY, MAY 8, 2024 AT 4:30 PM**

Members Present: *Chairperson Cheryl Kessel, Vice Chairperson Ben Kramer (via Zoom), and Commissioners - Robyn Aasmundstad, Becky Keck, and John Jones.*

Other Municipal Officials Present: *Joni Westcott, Parks and Recreation Director; Chell Smart, Parks and Recreation Specialist and Public Information Officer; Baileigh Cosmen, Parks and Recreation Coordinator.*

Audience: *Three members of the public were present in the audience or on zoom.*

- 1. CALL TO ORDER** – Chairperson Kessel called the meeting to order at 4:30 p.m.
- 2. ROLL CALL** – All members were present.
- 3. PUBLIC COMMENT** – One public comment from Cynthia Malla asking about details on the low water lawn in the Selna Mongini Park plan.

4. MINUTES

A. Approval of Minutes

Discuss, consider and act upon the draft minutes from the regular meeting held on March 18, 2024.

Action: **Approval of minutes.**

Motion: *Commissioner Aasmundstad*

Second: *Commissioner Keck*

Vote: Approved 5-0

Voting Member	Aye/Nay
Chairperson Cheryl Kessel	Aye
Vice Chairperson Ben Kramer	Aye
Commissioner Robyn Aasmundstad	Aye
Commissioner Becky Keck	Aye

5. DISCUSSION ITEMS ONLY - NO ACTION TAKEN

A. Selna Mongini Park Plan

Discussion was had regarding Selna Mongini Park hardscape and landscape plans and playground options were reviewed. Director Westcott noted that due to budget considerations and public input the originally proposed pickleball courts have been removed which freed up space for the zipline track to be moved closer to other active play areas.

Commissioners noted the importance of accessibility and shade to maximize usage.

See attached document: Selna Mongini Landscape and Hardscape Plan.

See attached document: Pavilion Ideas and Seating.

See attached document: Selna Mongini Park Playground Options.

Director Westcott addressed the public comment inquiry about the low water lawn by stating that the final decision has not been made between a low water seeded lawn or artificial turf. The Town is researching options for future use of reclaimed water at the park. Chairperson Kessel reopened the meeting for Public Comment and Cynthia Malla followed up with a statement of concern regarding heat and artificial turf.

9. FUTURE AGENDA ITEMS

Director Westcott noted the following future agenda items:

Commissioner reports as a standing agenda item.

Fourth of July

10. ADJOURNMENT – Chairperson Kessel adjourned the meeting without objection at 5:30 p.m.

Chairperson, Cheryl Kessel

SUBMITTED BY:

Parks and Recreation Specialist and Public Information Officer, Chell Smart

Values

Values are the guiding principles that provide an organization with purpose and direction. The Town of Clarkdale's organizational values are:

COPPER

Customer focused

Open, transparent and equitable

Preserving our history, charm, and environment
Planning for a sustainable future
Economic and social resiliency
Resourceful and innovative

Mission

The Town of Clarkdale serves the community by providing amenities, infrastructure, services, and public safety to enhance quality of life. We are stewards of our history while we sustainably and resiliently plan for the future with an emphasis on community engagement and transparency.

Persons with a disability may request reasonable accommodations by contacting the Town Hall at (928) 639-2400 (TTY: 1-800-367-8939) at least 72 hours in advance of the meeting.

LEGEND

-  LIGHT POLE (14 TOTAL) SPEC. BY CITY OF CLARKDALE.
-  TRASH RECEPTACLE (7 TOTAL) SPEC. BY CITY OF CLARKDALE.
-  PUBLIC ART LOCATIONS. OPTION TO DESIGN THE WATER TANK AND CONVEYANCE AS ADDITIONAL PUBLIC ART OR SUBSTITUTION FOR ONE OF THESE FOUR.



PRELIMINARY – NOT FOR CONSTRUCTION


NEW WEST WORKSHOP

t. 928.583.4481
t. 928-899.6489
www.newwestworkshop.com
3019 37th St.
Lubbock, TX 79413

SELNA-MONGINI PARK
CLARKDALE, ARIZONA

PROJECT: 2307
DATE: 03.07.24
REVISIONS:

L1.0



HARDSCAPE PLAN

SCALE: 1" = 20'-0"



KEYNOTES

- 1

BASKETBALL COURT - 82' x 50' post tensioned slab. With 5'-3" run out around entire court. By City of Clarkdale vendor. See Civil.
- 2

BOULDER RETAINING WALL. See Civil.
- 3

DECOMPOSED GRANITE PATH/SURFACE. 4' W. See Dtl. See dimension plan for width.
- 4

CONCRETE PATH/SURFACE. 5' Paths to be 4" Th. 6' Paths to be 6" Th. Control joints as shown. See Civil.
- 5

CONCRETE PAVER. Holland Stone. Manuf. - Yavapai Block 1389 Masonry Way Prescott, AZ 86301 800-649-4340. See Dtl. Color - TBD
- 6

NEW CONCRETE STAIR TO UPPER SIDEWALK. With handrails. See Civil.
- 7

ZIPLINE PLAY AREA. Finish w/ Fibar engineered playground surface over landscape fabric or equal. By City of Clarkdale Vendor.
- 8

TOT LOT PLAY AREA. Finish w/ Fibar engineered playground surface over landscape fabric or equal. By City of Clarkdale Vendor.
- 9

BIG KID PLAY AREA. Finish w/ Fibar engineered playground surface over landscape fabric or equal. By City of Clarkdale Vendor.
- 10

LARGE PAVILION. 40' dia. By City of Clarkdale Vendor.
- 11

EVENT LAWN. 7,780 SF. See planting plan.
- 12

HOME PLATE PLAQUE. By City of Clarkdale.
- 13

HOME PLATE SHADE STRUCTURE. By City of Clarkdale Vendor.
- 14

ART WALL. See dtl.
- 15

EXISTING DUGOUT RE-IMAGINED. See dtl.
- 16

DECORATIVE FENCE AS GRAPE TRELLIS. See dtl.
- 17

ENTRY MONUMENT SIGNS. See dtl.
- 18

RESTROOM. By City of Clarkdale Vendor.
- 19

RAIN TANK DEMONSTRATION. 10' dia. W/ informative signs. See dtl.
- 20

BOULDER CLAD SLOPE. Approx. 5' vert. See dtl.
- 21

RETAINING SITTING WALL. See civil. 3' H. max.
- 22

STONE LINED RAINWATER COLLECTION PLANTERS. See dtl.
- 23

ADDITIONAL NEW PARKING. (20) spaces. See civil.
- 24

NATURAL BOULDER BOLLARDS.
- 25

EX. PICNIC STRUCTURES
- 26

EX. HORSESHOE PITS
- 27

PASSIVE RAINWATER COLLECTION BASINS. Level bottom basin, 8"-12" D. See dtl.
- 28

EXISTING CONCRETE SIDEWALK
- 29

DG PAD FOR TEMPORARY PORTABLE TOILETS
- 30

8"x8" REINFORCED, EXTRUDED CONC. CURB FLUSH W/ TOP OF CONC. WALKS.
- 31

BENCH - SOLID SANDSTONE SLAB
20-24" W X 18" H X 60" L
- 32

PICNIC TABLE. SPEC BY CITY OF CLARKDALE.
- 33

BIKE RACK/PARKING. See Civil.
- 34

FIELD VERIFY NUMBER OF CONCRETE STEPS REQ'D.
- 35

EX. DUGOUT - NO WORK/CHANGES TO BE MADE.
- 36

EXISTING CONC. PAD TO REMAIN.
- 37

TIE NEW CONC. SIDEWALK INTO EXISTING. FLUSH.
- 38

CROSSWALKS BY TOWN OF CLARKDALE.

GENERAL NOTES

1.

The contractor shall locate and verify the location of all utilities prior to starting work.
2.

Verify all questionable or conflicting dimensions or conditions prior to construction.
3.

Crushed rock to be 3" minimum layer of 3/4" Cactus Berry gravel.
Source: Arrowhead Mining and Materials P.O. Box 3660 Chino Valley, Arizona 86323 (928) 636-5844
Broadcast and water in organic pre-emergent into gravel during installation at recommended rate (see note 4).
4.

Organic Pre-emergent: Use 'Concern Weed Prevention Plus (or equal) at a rate of 20# per 1000 sq. ft., and applied as suggested by manufacturer. Apply organic pre-emergent to all crushed rock areas. Apply at time of installation.
Source: Necessary Organics 8906 Wentworth Ave. S Minneapolis, Minnesota 55420 1-800-468-2472
5.

The plan shall take precedence over the plant list in the event of a discrepancy.
6.

Control weeds as needed after installation.

GENERAL CONSTRUCTION NOTES

1.

The positions of existing underground utilities as shown on the construction plans were determined from site inspection, and other "Best Available" information. The contractor shall contact "Blue Stake" for utility location and carefully excavate (including potholing if required) to determine the true horizontal and vertical positions of utilities. The contractor is responsible for protecting existing utilities and shall notify the owner of any conflicting conditions.
2.

All construction shall conform to the Maricopa Association of Governments Specification and Details, 1994 revisions, and Yavapai Association of Governments (Y.A.G.) Detail Drawings.
3.

All existing underground utilities shown are approximate and are to be verified by each Subcontractor. Owner does not accept any responsibility for the accuracy of the location of existing utilities indicated on the Drawings. Verify location of existing utilities and exercise every precaution when working on or near these areas, to avoid damage to those existing facilities. Utility lines may be encountered in excavations that were not known (or shown or exist), so caution should be taken in all excavations. Active or inactive utilities encountered shall be handled in accordance with the requirements of the utility companies.
4.

Prior to bidding the work, the Contractor shall thoroughly satisfy himself as to the actual conditions and requirements of the work. No claim shall be made against the Owner or the Engineer for any alleged misunderstanding of the conditions or nature of the work.
5.

Nothing contained in the construction drawings shall create, nor shall be construed to create, any contractual relationship between the Engineer and the Contractor or any Subcontractor.
6.

The Landscape Architect will not be responsible for construction means, methods, techniques, sequences or procedures or for safety precautions or programs utilized in connection with the work.
7.

It is the sole responsibility of the Contractor to obtain, at his own expense, such permits as are required from the appropriate agency.
8.

The Landscape Architect shall be notified 24 hours prior to beginning any construction.
9.

Work not in conformation with the plans and specifications is subject to removal and replacement at the Contractor's expense.
10.

It shall be the responsibility of the bidder to verify all quantities, including excavation, borrow, embankment, shrink or swell, ground compaction, haul and any other items affecting his bid and to base his bid solely upon his own verified quantities, irrespective of the information furnished. It shall be the bidder's responsibility to notify the Engineer prior to bidding of any major discrepancies.
11.

Disposal and/or stockpiling of excess material shall be done in such a way that will not create a nuisance. The placing of material on private property of another requires written authorization.
12.

Borrow material should be free of debris, organic materials, and three-inch size (3-inch particles or larger. We recommend fill material conform to the following general specification or approved equal:

US STANDARD SIEVE PERCENT PASSING
3.0-Inch 100
NO. 40 40-60
NO. 200 0-30
The Plasticity Index should be between 2 and 15 unless otherwise specified in the project soils report.
13.

The Contractor shall provide construction staking and careful grade control and grade checking with finish as-built plans as required to provide proper drainage.
14.

All subgrade materials shall be scarified to a depth of eight inches (8"), the moisture content adjusted to near optimum, then compacted to 95% of ASTM D-698.
15.

Clearing and grubbing shall extend to the limits of grading and construction shall be in accordance with MAG Specification, Section 201.
16.

Trench excavations, backfilling and compaction shall conform to MAG Specification 601, Type 1, unless noted otherwise.
17.

All fill shall be crushed stone or granular fill with less than 8% passing the #200 sieve.
18.

Fill shall be deposited in no greater than 6" horizontal lifts, and each layer compacted uniformly to 95% standard optimum density per ASTM D-698.
19.

Material/quality:
- Minimum compressive strength: 2500 PSI @ 28 days
- Transit mix must conform to ASTM C94: Min: cement 6 bags/c.y.
- Slump: 3" to 5"
- Air entrainment: 3-5% by volume
- Cement: Type I or II, gray
- Reinforcing steel - ASTM A615 Grade 60: Deformation per ASTM A305
- No chloride or other unauthorized admixtures shall be used
- Field testing to be paid for by Owner
20.

Masonry (Concrete Block): hollow, light weight concrete masonry units per ASTM C90, Grade N, Type 1, Fm = 1900 psi, Mortar Type S, Grout psi construction to conform to UBC Chapter 21 with no special instruction provided.
21.

Reinforcing: Bars #5 and smaller ASTM A615, Grade 40; Bars #6 and larger ASTM A615, Grade 60; #5 Bars and smaller in precast concrete or elevated floor slabs or beams shall be grade 60 welded wire fabric ASTM A185 and A 82 clear cover and lap lengths per ACI and UBC.
22.

Finishing - all slabs to be steel trowel except for ramps which will be a light broom finish perpendicular to slope.
23.

Curing shall be wet cured in accordance with an approved ACI curing method. Curing compounds may be allowed upon approval by the Engineer.
24.

Fill all holes; rub finish on all exposed walls.

DETAILS LIST

DG PATH
artwall
existing dugout
decorative fence
rainwater tank
entry monuments
boulder clad slope
zuni bowls
rainwater basins



PRELIMINARY – NOT
FOR CONSTRUCTION

NEW WEST WORKSHOP

t. 928.583.4481
t. 928-899.6489
www.newwestworkshop.com
3019 37th St.
Lubbock, TX 79413

SELNA-MONGINI PARK
CLARKDALE, ARIZONA

PROJECT: 2307
DATE: 03.07.24
REVISIONS:

L1.1


SELNA-MONGINI PARK
CLARKDALE, ARIZONA

PROJECT: 2307
DATE: 03.07.24
REVISIONS:






L2.0



PLANTING PLAN



PLANT PALETTE


SYMBOL	CODE	BOTANICAL NAME	COMMON NAME	SIZE	CONTAINER	QTY	DETAIL	REMARKS	
ADAPTIVE TREES									
	CHI BBB	Chilopsis linearis	Bubba	24"	Box	2		Multi-Stemmed	
	CUP ARI	Cupressus arizonica 'Blue Ice'	Blue Ice Arizona Cypress	25 gal.	B&B	7			
	GLE IN4	Gleditsia triacanthos inermis	Thornless Honey Locust	4" Cal.	B&B	6			
	JUN SIN	Juniperus monosperma	Oneseed Juniper	6' Ht.	B&B	5			
	MAL COA	Malus x 'Pink Robinson'	Pink Robinson Crabapple	1.5" Cal.	Pot	8		Pink	
	MAL SPR	Malus x 'Spring Snow'	Spring Snow Crab Apple	1.5" Cal.	Pot	3		White	
	PIN PIN	Pinus edulis	Pinyon Pine	6' Ht.	B&B	2			
	PRO VEL	Prosopis velutina	Velvet Mesquite	3" Cal.	Box	6			
	PRU PER	Prunus spp.	Peach spp.	15 gal.	Pot	2			
	ROB ROB	Robinia pseudoacacia 'Purple Robe'	Purple Robe Black Locust	3" Cal.	B&B	7			
	VIT CHA	Vitex agnus-castus	Chaste Tree	15 gal.	Pot	4			
NATIVE TREES									
	CHI LIN	Chilopsis linearis	Desert Willow	15 gal.	Pot	2		Chilo	
	QUE EMO	Quercus emoryi	Emory Oak	3" Cal.	B&B	2			
ADAPTIVE SHRUBS									
	CAE GIL	Caesalpinia gilliesii	Yellow Bird of Paradise Bush	15 gal.	Pot	9			
	ERI TUR	Ericameria laricifolia	Turpentine Bush	5 gal.	Pot	9			
	LEU GRE	Leucophyllum frutescens 'Green Cloud'	Green Cloud Texas Sage	5 gal.	Pot	4			
	LEU FRU	Leucophyllum frutescens 'Ranger'	Ranger Texas Sage	5 gal.	Pot	17			
	ROS PRO	Rosmarinus prostrata	Creeping Rosemary	5 gal.	Pot	11			
	SAL GRE	Salvia greggii	Autumn Sage	5 gal.	Pot	3			
CACTI AND SUCCULENTS									
	HES PAR	Hesperaloe parviflora	Red Yucca	5 gal.	Pot	24			
	YUC PEN	Yucca pendula recurvifolia	Soft Tip Yucca	5 gal.	Pot	3			
NATIVE SHRUBS									
	DAL FOR	Dalea formosa	Featherplume	5 gal.	Pot	3			
	LAR TRI	Larrea tridentata	Creosote Bush	5 gal.	Pot	5			
	NOL MIC	Nolina microcarpa	Beargrass	5 gal.	Pot	25			
	TAG LEM	Tagetes lemmonii	Mount Lemon Marigold	5 gal.	Pot	15			
	VAU CA2	Vauquelinia californica	Arizona Rosewood	5 gal.	Pot	8			
VINES									
	TRA ST2	Trachelospermum jasminoides 'Star'	Star Jasmine	15 gal.	Pot	6			
	VIT THO	Vitis vinifera 'Thompson Seedless'	Thompson Seedless European Grape	5 gal.	Pot	4			
SYMBOL	CODE	BOTANICAL NAME	COMMON NAME	SIZE	CONTAINER	SPACING	QTY	DETAIL	REMARKS
GROUND COVERS									
	CYN MI2	Cynodon dactylon 'Midiron'	Midiron Bermudagrass	sod			7,439 sf		
PLANTED AREAS									
	BUT GAR	Butterfly Gardens		---					

PLANTING NOTES

1. DESCRIPTION OF WORK: Landscape Contractor shall provide all labor, plants, materials and equipment including all soil amendments, tree protection material and inert mulches necessary to install the work indicated on the planting plans. They shall inspect the plans and the site, and shall install all landscape elements per the intent of the plan. Any discrepancies noted shall immediately be brought to the attention of the Owner's Agent for resolution.
2. SUPERVISION: Landscape Contractor shall maintain a qualified supervisor on the site at all times during construction through completion of punch list items.
3. The contractor shall supply all plant materials in quantities sufficient to complete the planting shown on all drawings. No plant substitutions will be accepted without pre-approval from the Landscape Architect.
4. Plant material shall be first class nursery stock conforming in size and grade to American Association of Nurserymen.
5. No plant shall be put into the ground before rough grading has been finished and approved by the project architect or equal.
6. Tree and shrub pits shall be three times the width of the ball, bottom of ball to rest on tamped planting mix as in planting detail.
7. Planting mix to consist of 3 parts native soil and 1 part humus.
8. Native soil shall be free from clods, stones and any other undesirable material larger than 2" in diameter.
9. Humus shall be commercial composted mulch material, dark brown to black and able to pass through a 1/2" screen.
10. Fertilizer for tree pits, shrub beds and vines shall be continuous release organic fertilizer, mixed with soil according to recommended rates as per the manufacturer. Add Mycorrhizal Landscape Inoculant (LA) or equal. 1 tsp./planting hole. Apply as suggested by manufacturer. Source: Bio Organics Mycorrhizal Inoculants, 53606 Bridge Dr., La Pine, Oregon 97739, 1-888-332-7676
11. All plants shall bear the same relationship to finished grade as the plant's original grade before digging.
12. All plants shall be balled and wrapped or container grown as specified. No container grown stock will be accepted if it is root bound. All root wrapping material made of synthetics or plastics shall be removed at the time of planting.
13. With container grown stock, the container shall be removed and the container ball shall be cut through the surface in four vertical locations.
14. All trees shall be staked with 2 Lodgepole Pine stakes, 8' long, set plumb in the ground. Stakes are not to pierce rootball. Stretch tape ties will not be accepted. Stake in accordance with acceptable horticulture practices for windy, open locations.
15. All plants shall be installed as per details and the contract specifications.
16. All plants and stakes shall be set plumb unless otherwise specified.
17. MAINTENANCE: Contractor shall provide job maintenance immediately following any planting operation and shall continue until job acceptance by Owner. All plants are to be watered thoroughly twice during the first 24-hour period after planting and then irrigated once every two days for a 30 day period. Length of watering time to be determined by checking soil moisture content. Watering is needed if soil is dry down 3" from soil surface. Watering duration should be from 1 hour to 2 hours. All trees, shrubs and groundcover shall then be irrigated once a week minimum or as needed to maintain health. Plants are spaced to allow full natural growth without the need of regular pruning. Prune only for safety reasons and annual tree thinning. Restore planting saucers as needed. Tighten and repair stakes; reset trees and shrubs to proper grades or vertical position as required. Weed as required. After all landscape operations are complete and in conformance with the contract documents, the Owner shall grant provisional acceptance. Following provisional acceptance, the Contractor shall provide job maintenance for 90 days consisting of all items covered under maintenance above. Following the 90-day maintenance period, the Owner shall grant final job acceptance after verifying all work and plants are in conformance with the contract documents.
18. GUARANTEE: All plants to be guaranteed for one year following final job acceptance by Owner. Any unhealthy plants shall be promptly removed and replaced. All other plants to be guaranteed for six months following final acceptance by Owner. All other materials and workmanship to be guaranteed for a period of one year following final job acceptance by Owner. Guarantee will be limited to one replacement unless it is determined that faulty plant materials or workmanship are the cause of need for replacement.

DETAILS LIST

TREE AND SHRUB
TREE AND SHRUB SLOPE
STAKING



PRELIMINARY – NOT
FOR CONSTRUCTION

NEW WEST WORKSHOP

t. 928.583.4481
t. 928-899.6489
www.newwestworkshop.com
3019 37th St.
Lubbock, TX 79413

SELNA-MONGINI PARK
CLARKDALE, ARIZONA

PROJECT: 2307
DATE: 03.07.24
REVISIONS:

L2.1







Selna Mongini Park

Clarkdale, AZ



ARIZONA RECREATION DESIGN, INC.



www.littletikes.com
© & © The Little Tikes Company U.S. and other countries.


2-5 Playground Option #1

2-5 Playground


Option #1:

Play Structure Features:


- 2 Bay Arch Swing with Integrated Shade, Inclusive Seat with Harness and Generation Seat
- (3) Unlimited Play Sensory Ramps
- ADA Transfer Station
- Overhead Bowed Ladder
- Vehicle Reach Panel
- Functionally Linking Pine Stumps
- Inch Worm Climber
- Nu Edge Crawl Log
- Boingo Panel
- Treehouse Pod Climber
- 36" Slide with Transfer Deck
- 48" Double Slide with Transfer Deck
- Stump Climber
- 36" Elbow Slide
- Arch Log Climber
- Integrated 26' Hexagon Shade and (2) Umbrella Shades




2-5 Playground Option #1




2-5 Playground Option #1



2-5 Playground Option #1



2-5 Playground Option #1



2-5 Playground

Option #1: Accessibility Chart

Age Group: 2-5			
Elevated Play Activities Total:	8		
Elevated Play Activities Accessible By Transfer:	8	Req'd:	0
Elevated Play Activities Accessible By Ramp:	8	Req'd:	4
Ground Level Activity Type:	6	Req'd:	0
Ground Level Quantity:	17	Req'd:	0


Description	Elevation	Access	Type of Play	Qty
KB TREEHOUSE POD CLIMBER 24"	Elevated	Ramp&Transfer	CLIMBER-B	1
LADDER BOWED CHALLENGE 1830 MM KB	Elevated	Ramp&Transfer	OVERHEAD-A	1
NU-EDGE 3 STUMP CLIMBER 40" KB	Elevated	Ramp&Transfer	CLIMBER-Q	1
NU-EDGE ARCH LOG CLIMB 40" KB	Elevated	Ramp&Transfer	CLIMBER-C	1
Reach Vehicle Panel	Elevated	Ramp&Transfer	PANEL-B	1
SLIDE DBL.WD. 1220 MM/48" KB W/SLALOM HOOD	Elevated	Ramp&Transfer	SLIDE-A	1
SLIDE ELBOW 70 DEG. KB	Elevated	Ramp&Transfer	SLIDE-A	1
SLIDE WAVE KB 915 MM/36" KB	Elevated	Ramp&Transfer	SLIDE-A	1
Generation Swing Seat ~ 8'	Ground	Ground	SWING	2
INCHWORM CLIMBER	Ground	Ground	CLIMBER	1
Inclusive Seat ~ 8'	Ground	Ground	SWING	1
Inclusive Seat ~ 8' (requires Harness for 2-5)	Ground	Ground	SWING	1
KB BOINGO PANEL	Ground	Ground	PANEL-D1	1
NU-EDGE CRAWL LOG FS	Ground	Ground	CRAWL	1
NU-EDGE STUMP BIRCH MEDIUM F/KB	Ground	Ground	BALANCE-D	1
NU-EDGE STUMP BIRCH MEDIUM F/KB	Ground	Ground	BALANCE-D	1
NU-EDGE STUMP BIRCH MEDIUM F/KB	Ground	Ground	BALANCE-D	1
NU-EDGE STUMP PINE SHORT F/KB	Ground	Ground	BALANCE-D	1
NU-EDGE STUMP PINE SHORT F/KB	Ground	Ground	BALANCE-D	1
NU-EDGE STUMP PINE SHORT F/KB	Ground	Ground	BALANCE-D	1
NU-EDGE STUMP PINE SHORT F/KB	Ground	Ground	BALANCE-D	1
PANEL ADJUSTABLE COUNTER KB	Ground	Ground	PANEL-C	1
Tot ~ Standard Beam 8'	Ground	Ground	SWING	1
Tot ~ Standard Beam 8'	Ground	Ground	SWING	1

2-5 Playground Option #2

2-5 Playground Option #2

Play Structure Features:

- 2 Bay Arch Swings with Integrated Shade, (2) Tot Seats, Inclusive Seat with Harness and Generation Seat
- Solo Spin
- Nectar Bumble Bee Rocker
- Unlimited Play Sensory Ramps
- Snake Pole Climber with Transfer Deck
- Overhead Bowed Ladder
- Functionally Linking Pine Stumps
- Black Bear Tunnel Climber
- Tucson Turtle Climber
- 36" Elbow Slide with Transfer Deck
- Treehouse Pod Climber
- Arch Log Climber
- Braille Clock Panel
- Treehouse Curly Climber
- Stump Climber
- 40" Elbow Slide with Transfer Deck
- 52" Slide with Transfer Deck
- ASA Transfer Station
- (4) Integrated Umbrella Shades




2-5 Playground Option #2



2-5 Playground Option #2



2-5 Playground Option #2



2-5 Playground

Option #2



2-5 Playground

Option #2: Accessibility Chart

Age Group: 2-5			
Elevated Play Activities Total:	9		
Elevated Play Activities Accessible By Transfer:	9	Req'd:	0
Elevated Play Activities Accessible By Ramp:	9	Req'd:	5
Ground Level Activity Type:	6	Req'd:	0
Ground Level Quantity:	13	Req'd:	0


Description	Elevation	Access	Type of Play	Qty
50-56 SGL WIDE SLD KB	Elevated	Ramp&Transfer	SLIDE-A	1
KB CLOCK BRAILLE PANEL	Elevated	Ramp&Transfer	PANEL-I	1
KB ELBOW SILDE 1016 mm LEFT 42-44	Elevated	Ramp&Transfer	SLIDE-A	1
KB TREEHOUSE CLIMBER CURLY 36"	Elevated	Ramp&Transfer	CLIMBER-B	1
KB TREEHOUSE POD CLIMBER 24"	Elevated	Ramp&Transfer	CLIMBER-B	1
NU-EDGE 3 STUMP CLIMBER 40" KB	Elevated	Ramp&Transfer	CLIMBER-Q	1
NU-EDGE ARCH LOG CLIMB 32" KB	Elevated	Ramp&Transfer	CLIMBER-C	1
POLE SNAKE 915 MM/36" KB W/WIRE ENCL	Elevated	Ramp&Transfer	CLIMBER-B	1
SLIDE ELBOW 70 DEG. KB W/2014 HOOD	Elevated	Ramp&Transfer	SLIDE-A	1
BLACK BEAR SLEEPING OVER LOG TUNNEL CLIMBER	Ground	Ground	CLIMBER	1
Generation Swing Seat ~ 8'	Ground	Ground	SWING	2
Inclusive Seat ~ 8'	Ground	Ground	SWING	1
Inclusive Seat ~ 8' (requires Harness for 2-5)	Ground	Ground	SWING	1
LADDER BOWED CHALLENGE 1830 MM KB	Ground	Ramp&Transfer	OVERHEAD-A	1
NECTAR THE BUMBLE BEE SPRING RIDER	Ground	Ground	RIDER	1
NU-EDGE STUMP BIRCH MEDIUM F/KB to 20" Deck	Ground	Ramp&Transfer	BALANCE-D	1
NU-EDGE STUMP PINE SHORT F/KB	Ground	Ground	BALANCE-D	1
NU-EDGE STUMP PINE SHORT F/KB	Ground	Ground	BALANCE-D	1
NU-EDGE STUMP PINE SHORT F/KB	Ground	None	BALANCE-D	1
NU-EDGE STUMP PINE SHORT F/KB	Ground	None	BALANCE-D	1
NU-EDGE STUMP PINE SHORT F/KB	Ground	None	BALANCE-D	1
PANEL ADJUSTABLE COUNTER KB	Ground	Ground	PANEL-C	1
SOLO SPINNER	Ground	Ground	BALANCE-G	1
Tot ~ Standard Beam 8'	Ground	Ground	SWING	1
Tot ~ Standard Beam 8'	Ground	Ground	SWING	1
TUSCON TURTLE CLIMBER	Ground	Ground	CLIMBER	1

5-12 Playground Option #1

5-12 Playground Option #1

Play Structure Features:

- Nu Edge Tower with 14' Morphous Slide and Diamond Climber
- Nu Edge Birch Arch Bridge (Stacked)
- Crazy Hoopla Bridge
- 96" Hypersonic Slide
- Tilted Rock Wall
- S Curve Bridge
- Double Wall Climber
- Treehouse Window Panel
- 48" Double Slide
- Deck to Deck Bumpy Climber
- Below Deck Steel Counter Panel
- Fire Escape Climber
- Cylinder Climber
- Below Deck Crawl Thru Panel
- Nu Edge Birch Climber
- 40" Elbow Slide
- Arch Log Climber
- ADA Transfer Station
- Boingo Panel
- Trail Climber
- Fan Climber
- Pedal Twist Climber
- 96" Quantum Spiral Slide
- 90 Degree Curved Bridge
- Nu Edge Roofs



5-12 Playground Option #1



5-12 Playground Option #1



5-12 Playground

Option #1



5-12 Playground

Option #1



Nu Edge Tower



5-12 Playground

Option #1: Accessibility Chart

Age Group: 5-12			
Elevated Play Activities Total:	19		
Elevated Play Activities Accessible By Transfer:	17	Req'd:	10
Elevated Play Activities Accessible By Ramp:	0	Req'd:	0
Ground Level Activity Type:	6	Req'd:	3
Ground Level Quantity:	14	Req'd:	6

*Play Structures with 20 or more elevated play activities MUST have a ramp.


Description	Elevation	Access	Type of Play	Qty
96" HYPERSONIC SLIDE F/KB	Elevated	Transfer	SLIDE-A	1
CLIMBER FAN 72"/1830mm F/KB	Elevated	Transfer	CLIMBER-C	1
CYLINDER CLIMBER 1625/64" KB	Elevated	Transfer	CLIMBER-B1	1
DECK TO DECK BUMPY CLIMBER	Elevated	Transfer	CLIMBER-E	1
KB CRAZY HOOPLA BRIDGE 2440MM (96")	Elevated	None	CLIMBER-T	1
KB DBL WALL CLIMBER 48"	Elevated	Transfer	CLIMBER-D	1
KB ELBOW SILDE 1016 mm LEFT 42-44	Elevated	Transfer	SLIDE-A	1
KB FIRE ESCAPE CLIMBER 96"	Elevated	Transfer	CLIMBER-I	1
KB QUANTUM II SPIRAL SLIDE LEFT	Elevated	Transfer	SLIDE-A	1
KB TILTED ROCK CHALLENGE WALL 96"	Elevated	Transfer	CLIMBER-H	1
KB TRAIL CLIMBER 72"	Elevated	Transfer	CLIMBER-D	1
LADDER RUNG 610 MM W/SAFETY LOOP KB	Elevated	None	CLIMBER-I	1
NU-EDGE ARCH LOG CLIMB 40" KB	Elevated	Transfer	CLIMBER-C	1
NU-EDGE BIRCH ARCH BRIDGE 8' F/KB	Elevated	Transfer	BRIDGE	1
NU-EDGE BIRCH CLIMBER F/KB 72â€³	Elevated	Transfer	CLIMBER	1
Nu-Edge X Tower F/KB	Elevated	Transfer	TOWER	2
PEDAL STEP CLIMBER W/WIRE ENCL	Elevated	Transfer	CLIMBER-I	1
SLIDE DBL.WD. 1220 MM/48" KB	Elevated	Transfer	SLIDE-A	1
KB BOINGO PANEL	Ground	Ground	PANEL-D1	1
KBP SEAT PANEL PTMT	Ground	Ground	PANEL-P	1
PANEL COUNTER F/STORE FRONT KB (STEEL)	Ground	Ground	PANEL-C	1
PANEL CRAWL/flat top/760 MM PTMT. KB	Ground	Ground	CRAWL	1
PANEL CRAWL/flat top/760 MM PTMT. KB	Ground	Ground	CRAWL	1
PANEL LADDER 610/24" SAFETY LOOPS BD KB	Ground	Ground	CLIMBER-I	1
PANEL LADDER 610/24" SAFETY LOOPS BD KB	Ground	Ground	CLIMBER-I	1
Plastic Wheel	Ground	None	WHEEL	1
Post Mounted Plastic Wheel	Ground	Ground	WHEEL	1
STEPPING STONES F/KB	Ground	Ground	BALANCE-D	1
STEPPING STONES F/KB	Ground	Ground	BALANCE-D	1
STEPPING STONES F/KB	Ground	Ground	BALANCE-D	1
STEPPING STONES F/KB	Ground	Ground	BALANCE-D	1
STEPPING STONES F/KB	Ground	Ground	BALANCE-D	1
STEPPING STONES F/KB	Ground	Ground	BALANCE-D	1

5-12 Playground Option #2

5-12 Playground Option #2

Play Structure Features:

- Overhead Ring Ladder
- ADA Together Glider
- Overhead Funwheel
- 36" Double Slide with Transfer Deck
- 24" Ladder Panel
- Functionally Linking Pine & Birch Stumps
- Stacked Timber Climber with Net
- Stump Climber
- (2) 48" Quantum Slides with Transfer Decks
- Frog Climber
- ADA Transfer Station
- Trail Climber
- Log Slice Climber
- Double Wall Climber
- Tree Climb
- Lumberjack Climber
- Deck to Deck Silo Climber
- 96" Quantum Slide
- 96" Quantum Spiral Slide
- Monkey Lean Out Seat
- Below Deck Hang Out Seats
- Below Deck Counter Panel
- Integrated 26' Hexagon Shade, 20'x20' Pyramid Shade and (2) Umbrella Shades



5-12 Playground Option #2



5-12 Playground Option #2



5-12 Playground Option #2



5-12 Playground Option #2



5-12 Playground

Option #2: Accessibility Chart

Age Group: 5-12			
Elevated Play Activities Total:	16		
Elevated Play Activities Accessible By Transfer:	13	Req'd:	0
Elevated Play Activities Accessible By Ramp:	11	Req'd:	8
Ground Level Activity Type:	9	Req'd:	0
Ground Level Quantity:	14	Req'd:	0

*Play Structures with 20 or more elevated play activities MUST have a ramp.

Description	Elevation	Access	Type of Play	Qty
KB DBL WALL CLIMBER 48"	Elevated	Ramp&Transfer	CLIMBER-D	1
KB MONKEY LEAN OUT RAIL DKMT	Elevated	None		1
KB QUANTUM II SPIRAL SLIDE LEFT	Elevated	None	SLIDE-A	1
KB TRAIL CLIMBER 48"	Elevated	Ramp&Transfer	CLIMBER-D	1
NU-EDGE 3 STUMP CLIMBER 40" KB	Elevated	Ramp&Transfer	CLIMBER-Q	1
NU-EDGE LOG SLICE CLIMBER 48" KB	Elevated	Ramp&Transfer	CLIMBER-B	1
NU-EDGE TREE 72" W/KB SAFETY LOOP	Elevated	Transfer	CLIMBER-I	1
Nu-Edge X Lumberjack 1830 = 72"	Elevated	Ramp&Transfer	CLIMBER-M	1
SILO CLIMBER W/WIRE ENCL- DECK TO DECK	Elevated	Transfer	CLIMBER-I	1
SINGLE FUNWHEEL	Elevated	Ramp&Transfer	OVERHEAD-F	1
SINGLE QUANTUM SLIDE (44-50) BURIED ONLY	Elevated	Ramp&Transfer	SLIDE-A	1
SINGLE QUANTUM SLIDE (44-50) BURIED ONLY	Elevated	Ramp&Transfer	SLIDE-A	1
SINGLE QUANTUM SLIDE (44-50) BURIED ONLY	Elevated	Ramp&Transfer	SLIDE-A	1
SINGLE QUANTUM SLIDE (94-96) BURIED ONLY	Elevated	None	SLIDE-A	1
SLIDE DBL. W.D. 915 MM /36" KB	Elevated	Ramp&Transfer	SLIDE-A	1
TOGETHER GLIDER	Elevated	Ramp&Transfer	CLIMBER-D	1
FROG CLIMBER	Ground	Ground	CLIMBER	1
KB HANG OUT	Ground	Ground	SEAT	1
LADDER RING CHALLENGE F/KB 2440	Ground	Ground	OVERHEAD-A	1
NU-EDGE BIRCH COUNTER PANEL F/KB	Ground	Ground	PANEL	1
NU-EDGE DBL STACKED TIMBER CLIMB W/NET	Ground	Ground	CLIMBER-H	1
NU-EDGE STUMP BIRCH MEDIUM F/KB	Ground	Ground	BALANCE-D	1
NU-EDGE STUMP BIRCH MEDIUM F/KB	Ground	Ground	BALANCE-D	1
NU-EDGE STUMP BIRCH TALL F/KB	Ground	Ground	BALANCE-D	1
NU-EDGE STUMP BIRCH TALL F/KB	Ground	Ground	BALANCE-D	1
NU-EDGE STUMP PINE SHORT F/KB	Ground	Ground	BALANCE-D	1
NU-EDGE STUMP PINE SHORT F/KB	Ground	Ground	BALANCE-D	1
PANEL ADJUSTABLE COUNTER KB	Ground	Ground	PANEL-C	1
PANEL LADDER 610/24" W/HAND LOOPS BD KB	Ground	Ground	CLIMBER-I	1
STEELKBP CRAWL PANEL PTMT	Ground	Ground	CRAWL	1

Custom Panels



These are some examples of custom signs/panels. They can be engraved or printed. They are both usually very cost effective if the design is not too complicated. The printed signs (D-back Gives Back example) can have more color and detail for less cost.

Below are the # of panels in each option that could be swapped for a custom panel. Ground level panels/signs are also a possibility and do not require safety or use zones.

2-5 Option #1: 0


2-5 Option #2: 1

5-12 Option #1: 4

5-12 Option #2: 1



- Designers and manufacturers of commercial playground equipment for schools, parks, landscape architects, and housing communities since 1979
- Industry-leaders in custom play space design
- Experts on inclusive playgrounds in partnership with Unlimited Play
- Durability guaranteed with superior finishes and state-of-the-art manufacturing processes
- First-class before and after sale services and excellent warranties
- Environmentally-friendly manufacturing to ISO 9001, 14001, and 18001 standards
- Equipment exceeding safety specifications by ASTM, SPSC, CSA, CPSIA, IPEMA, and EN



ARIZONA RECREATION DESIGN, INC.

- Providing turnkey commercial playground services since 2010, including play space planning, design, surfacing, installation, and maintenance
- Official Little Tikes Commercial representative for Arizona and New Mexico
- Large selection of playground equipment, surfacing options, site amenities, and shelters
- Hand-selected team of installation experts



THANK YOU



CARISSA THOMASSON
Arizona Recreation Design, Inc
Cell: (480) 370-0840
carissa@arizonarec.com





Staff Report

Item Number: 6.A.

Agenda Item:**Clarkdale's Old Fashioned Fourth of July Event**

Discuss, consider and act upon the Clarkdale Old Fashioned 4th of July event plan with all listed components and awards.

Staff Contact:

Joni Westcott, Parks and Recreation Director

Meeting Date:

May 23, 2024

Strategic Goal:

- Goal Area 1 – Preserve and celebrate Clarkdale’s unique, complex history.
- Goal Area 2 – Enhance the quality of life for residents, businesses, and visitors to Clarkdale.
- Goal Area 3 – Enhance the quality and availability of parks, recreation and cultural opportunities.

Background:

Clarkdale’s Old-Fashioned 4th of July celebration began in 1976 with a kids parade and ice cream social. It grew over the years, most recently the following components have been enjoyed by the public:

- Pancake breakfast 7 a.m.- 9 a.m. hosted by the Clarkdale Police Department and Verde Valley Fire District. This is a fundraiser for both organizations.
- Verde Valley Fire District fire truck rides 7:30 a.m.- 11 a.m.
- Free Children’s Carnival Games 9 a.m. hosted by Clarkdale Jerome School and sponsored by Salt River Materials Group.
- Food, information, retail sales vendor booths.
- Ice Cream Social - hosted by the Clarkdale Historical Society and Museum.
- Kids Parade 9 a.m. (Main Street from Clarkdale Jerome School to Town Hall).
- Parade prize announcements 9:40 a.m.
- Cottonwood Community Band 10 a.m.-11 a.m.

All event elements with exception of the bubble machine activity have been ongoing for years. The bubble machine was added as an activity for kids in 2018. Due to concerns about staffing the activity, and preservation of the Town Park grass, Staff has not determined whether the bubble machine will be included this year.

Prizes are awarded to the best decorated entries with an emphasis on awarding bikes, wagons, pets, and floats featuring the following Strategic Plan Values:

- Resourceful and innovative (originality).
- Small town charm.
- Preserving our history.
- Planning for a sustainable future.

Bikes, wagons, pets, floats, and group entries will receive fifteen ribbons with cash prizes:

- Blue (5 winners)
- Red (5 winners)
- White (5 winners)

This allows judges to award the top entries regardless of category.

Budget Impact:

\$1000 General Fund 01-5-2602-7700 Fourth of July
\$2500 General Donation 80-5-2600-8001 Fourth of July Sponsorship from Salt River Material Group.

Recommendation:

Staff recommend approval of the Clarkdale Old Fashioned 4th of July event plan with all listed components and awards.